

SECTION 05 7316

WIRE ROPE METAL RAILING

*This specification document contains pink hidden text which serve as notes to the specifier. If this text is not displayed on your Microsoft word document, select file – options – display and select hidden text. If the text is already displayed, no further action is necessary. Hidden text will only display on electronic version of document, it will not print unless the option to print hidden text is selected. **Delete this note upon completion of work.***

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Aluminum Railing with wire cable infill
- B. Stair and ramp guardrails with cable infill
- C. Balcony railings and guardrails with cable infill
- D. Wall mounted and guardrail mounted handrails.

1.2 RELATED SECTIONS

- A. Section 01 3515 – LEED Requirements
- B. Section 03 3000 - Cast-In-Place Concrete: Placement of sleeves cast in concrete.
- C. Section 04 2000 - Unit Masonry: Placement of anchors in masonry
- D. Section 05 5000 - Metal Fabrications: Furnishing of sleeves cast in concrete.
- E. Section 05 5100 - Metal Stairs: Handrails other than those specified in this section
- F. Section 06 1000 – Rough Carpentry: Placement of blocking in wall construction.
- G. Section 07 1300 – Sheet Waterproofing
- H. Section 09 9116 – Gypsum Board Assemblies: Placement of backing plates in stud wall construction

1.3 REFERENCES

- A. ANSI A1264.1 - Safety Requirements for Workplace Floor and Wall Openings, Stairs, and Railing Systems.
- B. ASTM A 492 - Standard Specification for Stainless Steel Rope Wire
- C. ASTM B 211 - Standard Specification for Aluminum and Aluminum-Alloy Bar, Rod, Wire.

- D. ASTM B 247 - Standard Specification for Aluminum and Aluminum Die Forgings, Hand Forgings and rolled Ring Forgings.
- E. ASTM B 429 - Standard Specification for Aluminum-Alloy Extruded Structural Pipe and Tube.
- F. ASTM E 935 - Standard Test Methods for Permanent Metal Railing Systems and Rails for Buildings.

1.4 DESIGN / PERFORMANCE REQUIREMENTS

- A. Comply with requirements of building authorities having jurisdiction in Project location and the following:
 - 1. Handrail Standard: ANSI A1264.1
 - 2. Occupational Safety and Health Administration - 29 CFR 1910.23 - Guarding floor and wall openings.
- B. Structural Performance: Engineer, fabricate, and install handrails, guardrails, and railing systems to withstand, when tested per ASTM E 935, loadings required by applicable building and safety codes but not less than the following:
 - 1. Design Loads: Design to the following requirements. Concentrated and uniform loading need not be applied simultaneously.
 - 2. Uniform load: 50 pounds per foot (74.3 kg/m) applied at the top in any direction.
 - 3. Concentrated load: 200 pounds (90.6 kg) applied at the top in any direction.

1.5 SUBMITTALS

- A. Submit under provisions of Section 01 3000 – Administrative Requirements, for submittal procedures
- B. Product Data: Manufacturer's data sheets on each product to be used, including:
 - 1. Preparation instructions and recommendations.
 - 2. Details of material and construction.
 - 3. Storage and handling requirements and recommendations.
 - 4. Installation methods and requirements.
- C. Shop Drawings: Submit shop drawings for fabrication and installation of metal railings. Include plans, elevations and detail sections. Indicate materials, methods, finishes and types of joinery, fasteners, anchorages and accessory items.

- D. Load Tests: Submit test results from ASTM E 935 conducted on the manufacturer's supplied system indicating compliance with required structural loading.
- E. Selection Samples: For each finish product specified, two complete sets of color charts representing manufacturer's full range of available colors and patterns.
- F. Manufacturer's Certificates: Certify products meet or exceed specified requirements.
- G. Closeout Submittals: Provide manufacturer's maintenance instructions that include recommendations for periodic cleaning and maintenance of all components.

1.6 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Minimum 10 years documented experience producing systems specified in this Section.
- B. Mock-Up: Provide a mock-up for evaluation of surface preparation techniques and application workmanship.
 - 1. Finish areas designated by Architect.
 - 2. Do not proceed with remaining work until workmanship, color, and sheen are approved by Architect.
 - 3. Refinish mock-up area as required to produce acceptable work.
 - 4. Accepted mock-ups shall be comparison standard for remaining Work

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Store products in manufacturer's unopened, properly labeled, original packaging until ready for installation.
- B. Store components to avoid damage from moisture, abrasion, and other construction activities.
- C. Keep handling to a minimum. Exercise caution to avoid damage to factory applied finishes.

1.8 SEQUENCING

- A. Ensure that products of this section are supplied to affected trades in time to prevent interruption of construction progress.

1.9 PROJECT CONDITIONS

- A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.

- B. Field Measurements: Take measurements of actual dimensions where necessary for fit without gaps. Indicate measurements on shop drawings.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Acceptable Manufacturer: Superior Aluminum Products, Inc.; 555 E. Main St., P. O. Box 430, Russia, OH 45363. Phone: 937-526-4065. Fax: 937-526-3904. Email: info@superioraluminum.com. Web: www.superioraluminum.com.

- 1. Product: Series 5C Pipe Cable Railing.

- B. Substitutions: Not permitted.

- C. Requests for substitutions will be considered in accordance with provisions of Section 01 6000 - Product Requirements.

2.2 PIPE CABLE RAILING

- A. Pipe Cable Railing Series 5C: 1-1/2-inch (3.81 cm) Schedule 40 pipe with 1.9 inch (4.83 cm) outside diameter creates a framework containing openings for cables. Horizontal pipe is connected to post via concealed fasteners. No joints shall be fastened via welding. All posts are single posts manufactured to withstand maximum tension levels.

- 1. Horizontal Pipe Rail

- a. Pipe: 1-1/2-inch (3.81 cm) Schedule 40 pipe with 1.9 inch (4.83 cm) outside diameter runs between posts and utilizes concealed fasteners.
 - b. Top rail shall be continuous through the full length of the system.

- 2. Guard Rail Posts:

- a. 1-1/2-inch Schedule 40 pipe (3.81 cm) with 1.9 inch (4.83 cm) outside diameter fully reinforced for tensioning of cables.
 - b. 1-1/2-inch Schedule 40 pipe (3.81 cm) with 1.9 inch (4.83 cm) outside diameter with reinforcement rebar inserts for positioning of cables and supporting handrails between tensioning posts
 - c. Each post to have pre-drilled holes, spaced 3 inches on center, to accommodate fittings or support the cable.

- 3. Height:

- a. Residential: 36 inches (91.44 cm)
 - b. Commercial: 42 inches (106.68 cm)

- c. As indicated on the Drawings
- 4. Base: Size to fit the posts specified
 - a. Heavy-Duty Surface Mount Base
 - b. Cover Flange for Embedded Posts
 - c. Side-Mount Corner Base
 - d. Side-Mount Base
 - e. As indicated on the Drawings.

2.3 CABLES AND CABLE HARDWARE

A. Cables.

- 1. Material: 1 x 19 Type 316 stainless steel strand, left-hand lay, per dimensional properties contained in MIL-DTL-87161.
- 2. Finish: PVC coated.
- 3. Diameter: 3/16-inch (4.8 mm) diameter cable with a minimum breaking strength of 4000 pounds (1814.37 kilograms).
- 4. Orientation:
 - a. Horizontal.
 - b. Slope parallel to stair pitch.
- 5. Cut to length with stainless steel factory attached connectors
- 6. Spacing: 3 inches on center.

B. Cable Hardware Components.

- 1. Material: Stainless steel, ASTM A276 and A479, SAE/AMS QQ-S-763, Type 316.
- 2. Type: Hardware substantially concealed inside end posts where practical.
- 3. Type: Swaged Tensioned Fittings.

2.4 HAND RAIL: Series 5H Mounted Hand Rail:

- A. Pipe: 1-1/2-inch (3.81 cm) Schedule 40 pipe with 1.9 inch (4.83 cm) outside diameter.
- B. Handrail to run continuously throughout the whole length of handrail system.
- C. Mount to wall, railing, or other structure by utilizing mounting plates.

- D. No components shall be fastened via welding.
- E. Handrail will be installed at a height of 34 – 38 inches above ramp surface.
- F. Clearance of a minimum 1 ½” shall exist between the wall or post surface and the handrail.
- G. Top and bottoms of handrail sections that stop at a landing, the handrail shall extend 12 in horizontally beyond the top riser and 12 in. horizontally beyond the bottom tread.
- H. Handrail shall be continuous, without interruption by newel posts or other obstructions.
- I. Handrails shall return to a wall, guard or walking surface

2.5 Gates

- A. Provide swinging gates of type and size indicated on the Drawings. Equip gates with manufacturer’s standard as required for complete functional operation.
 - 1. Construction:
 - a. Frame: Welded frame fabricated from post, top rail and bottom rail material.
 - b. Infill: Match the railing design and configuration.
 - 2. Size: As shown on the drawings
- B. Hardware:
 - 1. Hinges: Size and type as determined by manufacturer.
 - a. Minimum of two hinges per leaf
 - 2. Latch
 - a. Lock Latch
 - b. Magna Latch

2.6 RAILING MATERIALS

- A. Rail, Post and Pickets: Aluminum extrusions; alloy and temper 6063-T4 or 6063-T6 for rail, posts, and pickets.
 - 1. Pipe: ASTM B 429.
- B. Base Flanges, Anchors, and railing accessories: ASTM B 247.

1. Bases cast from manufacturer's standard A-356-T6, 535, or 713 aluminum alloys or solid extruded 6063 aluminum alloy stock.
 2. Base flanges and railing accessories cast from manufacturer's standard 319, A-356, A-356-T6, 535, or 713 aluminum alloys.
 3. Anchorages: Provide anchorage for fastening and complying with applicable Federal standards. All fasteners used in the system shall be aluminum or stainless steel.
- C. Fasteners: Provide anchorage for fastening and complying with applicable Federal standards. Fasteners used in the system shall be aluminum or stainless steel.
- D. Grout: Non-shrink Portland cement-based hydraulic grout, mixed and applied in accordance with manufacturer's instructions; gypsum-based material is not acceptable. Provide formulation that is resistant to erosion from water exposure without needing protection by a sealer or waterproof coating and recommended by manufacturer for exterior use.

2.7 FINISH

- A. Standard Painted Architectural Coating (AAMA 2603):
1. White
 2. Black
 3. Dark Bronze
 4. Sandstone
 5. Custom colors as selected.
- B. Satin Anodized Finish:
1. 15 Minute: Architectural Clear Anodic Coating, AA-M12-C22-A21
 2. 60 Minute: Architectural Class I, AA-M12-C21-A41
 3. 60 Minute Brushed: Architectural Class I, AA-M35-C22-A41
- C. Duranodic Architectural Hard Coat Anodized Finish, AA-M12-C22-A42
1. Dark Bronze
 2. Black
 3. Custom colors as selected.

2.8 FABRICATION

- A. Tolerances: Verify dimensions on site prior to shop fabrication for proper connection to building structure or substrate.
- B. Components or railing sections shall be fabricated to exact measurements specified through Drawings and field dimensions.
- C. Railing sections shall be fabricated at the manufacturing facility in largest practical site delivery.
 - 1. Sections that require no site assembling shall have with cable infill installed and tensioned.
 - 2. Sections requiring site assembling shall have cable infill installed loosely and ready for connection to aluminum frame with factory drilled posts, inserts and grommets.
- D. Tension all cables in the guard rail system to a minimum of 250 pounds.
- E. Pipe cuts shall be square and accurate for minimum joint-gap. Cuts shall be clean and free of chamfer, from deburring, nicks and burrs.
- F. Railings angled horizontally, machine castings to proper angle.
- G. Fabricate railing system to meet step railing requirements; riser and tread dimensions of the steps.
- H. Posts grouted in concrete to have one nominal 1/4 inch (6.0 mm) nominal diameter weep hole, 1/2 inch (12.0 mm) nominal above post collar, in the plane of the rail
- I. Provide components required for anchorage of framing. Fabricate anchors and related components of material and finish as required, or as specifically noted.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Do not begin installation until substrates have been properly prepared. Fully review the supporting structure and substrate to verify a structurally sound base for anchoring railing system.
- B. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.

3.2 PREPARATION

- A. Clean surfaces thoroughly prior to installation.
- B. Coordinate railing installation with installation of waterproof membrane or coating Specified in Section 07 1300 – Sheet Waterproofing.

- C. Ensure that adjacent surfaces, structures, and finishes are protected from damage by construction activities of this section.
- D. Use wood blocks and padding to prevent damage to railing members and fittings during erection.
- E. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.

3.3 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install components plumb and inline, accurately fitted, free of distortion or defects and securely anchored to building structure and/or substrate.
- C. Provide grounds, clips, backing materials, adhesives, brackets, anchors, and accessories necessary for a complete installation.
- D. Expansion Bolt Mounting: Anchor through base plates to concrete substrate.
- E. Sleeve Mounting:
 - 1. Arrange for casting of sleeves or core drill into concrete to provide holes for railing uprights.
 - 2. After setting, fill holes with hydraulic grout; brace members until grout is cured.
- F. Connect aluminum frame components in accordance with manufacturer's instructions.
 - 1. Tighten all fasteners so that completed aluminum frame is rigid and free of play at joints and component attachments.
 - 2. Connect cables to aluminum frame using factory installed connectors and tighten cables in accordance with manufacturer's instructions. Tension all cables in the guard rail system to a minimum of 250 pounds.
- G. Gates:
 - 1. Install gates and adjust hardware for smooth operation.
 - 2. After installation, test gate. Open and close a minimum of five times. Correct any deficiencies and adjust.
- H. Expansion Joints: Provide expansion joints for continuous spans in excess of 40 feet (12.0 m). Construct joints by deleting structural adhesive from one end of the spliced joint so that it is free to move in or out of the pipe. If a joint is provided

every 30 feet (9.0 m), the width of the gap should allow 1/8 inch (3.0 mm) expansion for each 40 degrees F (22 degrees C) of expected temperature rise.

3.4 ERECTION TOLERANCES

- A. Install railings plumb and level, securely fastened, with vertical members plumb.
 - 1. Maximum variation from plumb: 1/4 inch (6.0 mm).
 - 2. Maximum misalignment from true position: 1/4 inch (6.0 mm).
 - 3. Maximum misalignment between adjacent separated members: 1/8 inch (3.0 mm).

3.5 CLEANING

- A. Remove dust or other foreign matter from component surfaces; clean finishes in accordance with AAMA 609 and AAMA 610-02.

3.6 PROTECTION

- A. Protect installed products until completion of project.
- B. Touch-up, repair or replace damaged products before Substantial Completion.

END OF SECTION